

# Tasman

## Retaining Wall System



Prestige & Quality

Near Vertical Walls

Do It Yourself

No Concrete Footings

Flexible - 90° Corners, Steps,  
Straight or Curved Walls

Australian Owned, Designed and Manufactured.

# Tasman

## Retaining Wall System



**Tasman Wall Block**  
390mm x 225mm x 200mm  
13 per m<sup>2</sup>  
75 per pallet  
Code: 225-01



**Tasman Full Corner Block**  
145mm x 340mm x 200mm  
(Available in left or right)  
Left hand corner shown  
Code: 225-34




**Tasman Half Wall Block**  
190mm x 225mm x 200mm  
26.5 per m<sup>2</sup>  
150 per pallet  
Code: 225-03



**Tasman Half Corner Block**  
145mm x 235mm x 200mm  
(Available in left or right)  
Left hand corner shown  
Code: 225-14



**Tasman 200mm Capping Block**  
200mm x 225mm x 60mm  
5 per lineal metre  
300 per pallet  
Code: 60-230



**Fortrac® Geogrid**  
Roll size 2.50m W x 200m L  
Types available  
35/20-20; 55/30-20



**Tasman Full Cap**  
390mm x 225mm x 60mm  
2.5 per lineal metre  
120 per pallet  
Code: 60-240  
Note: These caps are made by another manufacturer and colour variation may occur between these caps and Baines blocks.



**Bull Nose Cap**  
585mm x 245mm x 50mm  
1.7 per lineal metre  
Code: 50-245  
Note: These caps are made by another manufacturer and colour variation may occur between these caps and Baines blocks.

PLEASE NOTE: For Tasman walls over 660mm high please seek specific engineering advice.

**\*Engineer's Design Program Available\***

Visit: [www.bainesmasonry.com.au/contactus](http://www.bainesmasonry.com.au/contactus)

(Complies with AS4678 & MA53)



Appin Stone



Charcoal



Oakdale



Penrose



Bushrock



Opal White



Red Rock



Yellow Rock

Colours displayed in this brochure are to be used as a guide only. Colours are as close as printing process will allow. Displays in stores may vary to actual colour due to batch variation. Obtain samples from Baines Masonry for current batch colour.

Care should be taken to order sufficient product to complete job at one time to avoid batch variation.

Surplus blocks not returnable. No claims after 7 days or once products have been incorporated in construction.

REFER TO DESIGN & INSTALLATION GUIDE OR WEBSITE FOR SPECIFICATIONS  
CHECK WITH YOUR LOCAL COUNCIL TO ENSURE ALL LOCAL BUILDING CODES ARE COMPLIED WITH



TAS-BMB1